Resetting 39214-754/Issue 3

After testing, reset the call point by interlocking the reset key with reset mechanism, which is located on the front face. Turn the reset key clockwise until the yellow and black striped indicator is no longer visible.

**Earth Continuity Plate** 

An earthing plate (Fig. 4) is provided to maintain earth continuity of metal conduits or cable glands. This must be placed behind the backbox prior to fixing the box to the wall.

Important Information

The use of lubricants, cleaning solvents or petroleum based products should be avoided. The O-ring, part no 31523-007 should be replaced when refitting or replacing the Waterproof cover.

**Transparent Hinged Cover** 

To provide additional protection against accidental operation, a Transparent Hinged Cover, part no 44251-189, is available or 44251-175 for multiples of 10. This can be fitted to the manual call point included with this auide.

#### **Dust Cover**

To ensure optimal performance, leave the dust cover on the product and remove on commissioning.

For further information, please refer to PP2458 which is available on request.

© Apollo Fire Detectors Limited 2012

Apollo Fire Detectors Limited, 36 Brookside Road, Havant, Hampshire, PO9 1JR, UK
Tel: +44 (0) 23 9249 2412 Fax: +44 (0) 23 9249 2754
Email: techsales@apollo-fire.co.uk Website: www.apollo-fire.co.uk



# Conventional Waterproof Manual Call Point Installation Guide



#### General

This guide describes the installation of the following products:

Part No	Product Name	Туре	Colour
55200-003	Conventional Waterproof Manual Call Point	Outdoor	Red
55200-004	Conventional Non-Stanard Waterproof Manual Call Point	Outdoor	Yellow

#### Installation

To view the installation video, please use the QR code above

Place the earthing plate behind the backbox (see Earth continuity plate section). Fit
the backbox to a flat surface using the four fixing holes. The cable entry holes should
be in the vertical plane. The backbox can be mounted with either the single or double
entry holes at the top (Fig. 1). Note: All MCP installation and securing screws have a
maxium tightening torque of 0.6Nm.

Note: Cable entry from the bottom of the call point is recommended if there is a possibility of moisture condensing within the conduit or cables.

- 2. Run the cables into the backbox and connect them to the terminal block as shown in Fig. 3. Ensure that functional earth/screen continuity is maintained.
- 3. The Element must be in the ACTIVATED position when either removing or replacing the Front Cover Assembly.

Connect the cables to the terminal block and ensure that the O-ring is correctly seated in the channel. Place the cover squarely over the backbox and tighten the 6 fixing screws with the 2.5mm hexagonal key (supplied) to lock the cover. **Do not use excessive force, do not over tighten screws**.

When reassembling the Front Cover Assembly the two lower clips are located first followed by the two top clips.

The Conventional Manual Call Point is a 'type A' call point and is suitable for outdoor use.

#### Wiring Details

To maintain the integrity of the enclosure it is essential that suitable IP67 cable glands be used.

A suitable thread sealant is recommended to maintain IP rating.

1




Fig. 1 Backbox

Fig. 2 Front cover




Fig. 3 Terminal block connection




Fig. 4 Earthing plate

# **Technical Information**

Alarm Resistor Fitted Alarm Current,  $470\Omega$  (max) Operating Voltage (max) Switch Contact Type Switch Contact Rating Operating Temperature

470Ω/680 Ω 80mA 33V DC Normally Closed 1A -30°C to 70°C

### **LED Indicator**

• Illuminated red in alarm

# Commissioning

The installation must conform to BS5839–1 (or applicable local codes).

Ensure that the deformable element is fitted to each call point before testing.

## **Troubleshooting**

Before investigating individual units for faults, it is important to check that the system wiring is fault free.

Many fault conditions are the result of simple wiring errors. Check all connections to the unit. Do not overtighten screws when mounting the backbox.

## Fault Finding

Problem
Control panel reports zone fault
Control panel reports alarm

MCP does not activate alarm

Possible Cause
Incorrect zone wiring
Detector removed
EOL device missing or incorrectly fitted
MCP not reset
Incorrect EOL device
Incorrect wiring
Incompatible control panel

#### **Routine Testing**

Push the centre of the Element (printed with two black arrows and a circle) until the yellow and black striped indicator is visible. Observe routine test requirements as specified in the applicable local codes.